BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work: -Improvements to drains and asphalting to roads in 2nd cross 10th cross, 11th cross 9th cross, 2nd main , 8th main, 9th main , 10th main, 12th main, 13th main, 11th Cross and 5th A main in A sector in ward No:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no 138, PWD SR 2014-15)	Cum	403.72	75.60	Rupess seventy five and paise sixty only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	1000.72	264.60	Rupess two hundred sixty four and paise sixty ony
3	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1.4.2(Item no4.3,Page no12,PWD SR 2014-15)	Cum	38.90	4847.04	Rupess four thousand eight hundred forty seven and paise four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
4	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with super plasterise @ 3lts conforming etc as per specification&direction of the engineer incharge of work(pwd sr2014-15,p.no13,sno4.11)	Cum	116.39	6065.28	Rupess six thousand sixty five and paise twenty eight only
5	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr 2014-15,p.no17,s.no 4.46)	Qtl	93.11	7905.60	Rupess seven thousand nine hundred five and paise sixty only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,lahour complete asperspecification. Specification no.KBS 4.6.2 (pwd sr2014-15,p.no15/4.31)	Sqm	819.00	292.68	Rupess two hundred ninety two and paise sixty eight only
7	KSRRB M400-17: Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification: 406 (PWD SR 2014-15 P.N.154 It 20.18)	Cum	659.22	1438.56	Rupess one thousand four hundred thirty eight and paise fifty six only

	Description	Unit	Approved Qty	KRIDL, BBMP,	
				Rate	Rate in Words
8	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (ITEMNO21.6,Page no157,PWD SR 2014-15)	Sqm	4083.00	35.21	Rupess thirty five and paise twenty only
9	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler, transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and alignment, rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethe desired compactionasperMORTHSpecificationclauseno508completeinallrespectscompleteasperspecifi cations.using100120THcapacity H.M.P with sensor paver gradingI(35-40mm) with 4.5% CRMB55grade(Itemno21.21.1,Pageno16 D 2014-15)	Cum	102.08	10195.20	Rupess ten thousand one hundred ninety five and paise twenty only
10	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	45.90	1498.00	Rupess one thousand four hundred ninety eight only
11	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 130, PWD SR 2014-15)	Cum	1404.44	68.04	Rupess sixty eight and paise four only

Signature of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

ಅಂದಾಜು ಮೊತ್ತ :- 49.99